

DEPARTMENT OF EDUCATIONDepEd Complex, Meralco Avenue, Pasig City

PROGRAM OF WORKS

BILL OF QUANTITIES

Date:

School I.D	:			Budget Allocation:					
Region	:			Engineering and Administrative Overhead:					
Division	:			Approved Budget for the Contract:					
Project Title	:	Completion Period:							
				Minimum Regu	ired Manpower:				
				General Foreman Welder					
	PROPOSED DEPED OUTDOOR LEDWALL STRUCTURAL FRAMING DESIGN				Helper Mason Painter				
Location	: Meralco Avenue, Pasig City			Minimum Required Equipment:					
				Hand Tools Welding Machine					
				One-Bagger Mixer Bar Cutter					
Item No.		%			Direc	t Cost	Adjusted	Adjusted	
	Description	of	Unit	Quantity			Unit	Total	
		Total			Total Cost	Unit Cost	Cost	Cost	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	
						(6) / (5)	(9) / (5)	. ,	
Α.	Facilities for the Engineer					. , , ,	, , ,		
A.1	Temporary Facilities		Month	1.50					
B.	Other General Requirements								
B.1	Fire Safety Inspection Certificate (FSIC)		lot	1.00					
SPL 1	Project Billboard		Each	1.00					
SPL 2	Construction Safety and Health		Month	1.50					
C.	Mobilization and Demobilization								
C.1	Mobilization and Demobilization		Ls	1.00					
1.0000	Earthworks								
1 (a)	Clearing and Grubbing		cu m	10.40					
1 (b)	Structural Excavation		cu m	15.60					
1 (c)	Backfilling of Excavated Materials		cu m	10.72					
1 (d)	Gravel Bedding G-1		cu m	1.04					
2.0000	Concreting Works								
2 (b)	Structural Concrete (Footing)		cu m	4.16					
2 (c)	Structural Concrete (Pedestal)		cu m	1.15					
3.0000	Rebar Works								
3 (a)	Reinforcing Steel Bar, Grade 40		kg	1,237.68					
4.0000	Formworks		Ū	,					
4 (a)	Installation and Removal of Formworks		sq.m	5.76					
, ,	Finishing Works								
5 (d)	Plain Cement Plaster Finish		sq.m	7.68					
7.0000	Steel Works								
	3" x 3" x 5/8" Angular bar		kg	2,220.24					
	Aluminum Composite Panel (ACP)		рс	9.00					
	1" x 1" x 1.2mm Tubular		рс	15.00					
	12" x 12" x 12mm Tubular		рс	2.00					
	12mm Steel Plate (0.45m x 0.45m)		рс	4.00					
	3/4" x 1' Anchor bolt (4)		рс	8.00					
13.0000	Painting Works								
	Metal Painting		lot	1.00					
	1								

Total Construction Cost

Prepared	l by: